

<sup>10</sup>  
KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

OCT 31 1963  
10-31-63  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Mack Oil Co.

Complete Address: 812 Union Center, Wichita, Kansas

Lease Name Weniger Well No. # 1

Location C NE NE Sec. 7 Twp. 29 Rge. 7 (E) (W) W

County Kingman Total Depth 4577

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Mack Oil Co.

Address: 812 Union Center, Wichita, Kansas License No.     

Operation Completed: Hour 3:00PM Day 29th Month Oct. Year 1963

The Above well was plugged as follows:

241' of 8 5/8" surface pipe, cemented with 200 sacks. Hole was filled  
with drilling mud to 250', 1st cementing plug, bridged with 1/2 sack hulls,  
cemented with 25 sacks. Hole was filled with drilling mud to 40', 2nd  
cementing plug, bridged with 1/2 sack hulls, cemented with 10 sacks to  
base cellar. Rat hole bridged and cemented with 2 sacks. Mouse hole  
bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

DATE 10/31/63  
INV. NO. 7995-11

Signed: Archie Elving  
Well Plugging Supervisor