

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 8 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Pickrell Drlg. Co.  
Complete Address 705 4th Natl Bldg. Wichita, Ks  
Lease Name Whitelaw Well No. 1  
Location C W 1/2 SW/SW Sec. 14 Twp. 29 Rge. 7 (E) (W) W  
County Kingman Total Depth 4480  
Abandoned Oil Well        Gas Well X Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Russ Casing Pulling Co. Inc.  
Address Box 1082 Great Bend, Ks License No. 623  
Operation Completed: Hour 4:30 PM Day 6 Month 1 Year 1971

The above well was plugged as follows:  
254 ft of 8 5/8 surface pipe cemented with 220 sacks. 4479 ft of 5 1/2  
long string cemented with 185 sacks. Top perf. 3723 ft. Sand back  
to 3700 ft, 5 sacks cement with bailer. Pulled 3590 ft of 5 1/2. Set  
10 ft rock bridge at 240 ft. Fill hole with 4 yds of redimix to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: A. Russell Riberstein  
Well Plugging Supervisor

DATE 1-8-71  
INV. NO. 3177-W