

KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

DEC 24 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Bachus Oil Company

Complete Address: 721 East Central, Wichita, Kansas

Lease Name Peggy Goetz Well No. # 1

Location NE SW NW Sec. 29 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 2685

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A      X     

This had been an oil well, abandoned, pipe pulled, Other well as hereafter indicated and plugged in 1962. Recently this hole had been washed down, and a completion failed.

Plugging Contractor: Flint Engineering and Construction Company

Address: Box 950, El Dorado, Kansas License No. 547

Operation Completed: Hour 10:00AM Day 23rd Month Dec. Year 1964

The Above well was plugged as follows:

367' of 8 5/8" surface pipe, cement circulated. 2516' of 2 1/2" tubing for long string, cemented with 125 sacks. Top perforation 2435'. All perforations were squeezed with 20 sacks of cement, to a pressure of 300 lbs, cement and plug was pumped in 2 1/2" to a depth of 2200'. When this hole was abandoned and plugged, prior to this, gas was a problem. About 975' of 5 1/2" was left in the hole from 990' to 16' of the ground level, and circulated with cement, through the surface pipe. Fluid level in the 5 1/2" was at 270', bridge plug was set on fluid at 270', and 20' of rock bridge, and cemented solid with 31 sacks, from 250' to the base of the cellar. 1925' of 2 1/2" tubing long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Ebling  
Well Plugging Supervisor

DATE 12/24/64

INV. NO. 393-11