

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Well Plugging Authority,
issued November 7, 1967.

Operator's Full Name Bachus Oil Company

Complete Address: 721 East Central, Wichita, Kansas 67202

Lease Name Goetz "B" Well No. # 1

Location NE SW SW Sec. 29 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 2762'

Abandoned Oil Well Gas Well X Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Company

Address: Box 950, El Dorado, Kansas 52175 License No. 547

Operation Completed: Hour 4:30PM Day 22nd Month November Year 1967

The Above well was plugged as follows:

360' of 8 5/8" surface pipe, cement circulated. 2517' of 4 1/2" long string,
cemented with 125 sacks. Plug back T.D. 2386'. Top perforation 2382'.
Bottom of the hole was sanded to 2350', and cemented with 4 sacks, through
the dump bailer. 1840' of 4 1/2" long string was recovered from the hole.
Hole was filled with mud to 225', rock bridge from 225' to 215', and
cemented with 25 sacks, with cement from 215' to 140'. Hole was filled
with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks,
with cement from 30' to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving
Well Plugging Supervisor

INVOICED

DATE 11-28-67

INV. NO. 6752-W