

10  
KANSAS  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

FEB 4 1963

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Morgenstern and Spector

Complete Address: P. O. Box 661 Russell, Kansas

Lease Name Goetz Well No. # 1

Location NE SW SW Sec. 29 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4429

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Knight Casing Pulling

Address: P. O. Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 6.00PM Day 1st Month Feb. Year 1963

The Above well was plugged as follows:

4429' of 5 1/2" long string cemented with 150 sacks, Plugged back to 4413'.  
Top of perferation 4394'. Hole sanded to 4385'. 360' of 8 5/8" surface  
pipe. 86 sacks of drilling mud was put in hole to kill gas. 10' rock  
bridge was set at 200' cemented with 20 sacks. Hole was filled with mud  
to 40' and 10' rock bridge, cemented with 10 sacks to base cellar

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving  
Well Plugging Supervisor

DATE 2/4/63  
INV. NO. 6516-W