

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 24 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Goetz Well No. # 2

Location SE NE SW Sec. 29 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4430

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Co.

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 2:00PM Day 23rd Month Jan. Year 1964

The Above well was plugged as follows:

211' of 8 5/8" surface pipe, cemented with 150 sacks. 4429' of 5 1/2" long
string, cemented with 100 sacks. Top perferation 4395'. Bottom of hole
was sanded to 4380', and cemented with 5 sacks. Fluid in hole was bailed
to 260'. Plug was set at 260', with 10' rock bridge, and cemented with
25 sacks, bringing the cement to 195' in the surface pipe. Hole was fill-
ed with mud to 40', 10' rock bridge, and cemented with 10 sacks to base
of cellar.

3660' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/28/64

INV. NO. 8531-W

Signed: Archie Elving
Well Plugging Supervisor