

14
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name D & M Drilling Co., c/o W. M. Barnett

Complete Address: Box 847, Great Bend, Kansas

Lease Name Goetz Well No. # 1

Location NW NW SW Sec. 29 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4006

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pilling Inc.

Address: Box 221, Great Bend, Kansas License No. 49

Operation Completed: Hour 10:00AM Day 26th Month Feb. Year 1964

The Above well was plugged as follows:

203' of 8 5/8" surface pipe, cemented with 150 sacks. 4000' of 5 1/2" long
string, cemented with 125 sacks. Top perforation 3975'. Bottom of hole
was sanded to 3950', and cemented with 5 sacks. Hole was bailed down to
240'. Plug was set at 240', with 10' rock bridge, and cemented with 30
sacks, bringing the cement to 145' in the surface pipe. Hole was filled
with mud to 40', with 10' rock bridge, and cemented with 10 sacks to
base cellar.

3610' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 2/28/64
INV. NO. 8416-W