

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION

JAN 20 1964  
1-20-64  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Santa Fe Pipe & Supply

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name Goetz Well No. # 3

Location NW NE SW Sec. 29 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4483

Abandoned Oil Well      Gas Well X Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Ace Pipe Pulling Co.

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 4:00PM Day 17th Month Jan. Year 1964

The Above well was plugged as follows:

200' of 8 5/8" surface pipe, cemented with 175 sacks. 4482' of 5 1/2" long string, cemented with 100 sacks. Plug back to 4434'. Top perforation 4410'. Bottom of hole was sanded to 4400', and cemented with 5 sacks. Bailed hole down to 275'. Plug was set at 275' with 10' rock bridge, cemented with 35 sacks. Hole was filled with mud to 40', 10' rock bridge, cemented with 10 sacks to base cellar.

The first plug at 275' was cemented with 35 sacks, bringing the cement to 175' in the surface pipe. 3700' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

DATE 1/21/64

INV. NO. 8480-W

Signed: Archie Elving  
Well Plugging Supervisor