

14
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

DEC 16 1963
12-16-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Santa Fe Pipe & Supply

Complete Address: P. O. Box 562, Great Bend, Kansas

Lease Name George Carter Well No. # 1

Location NE NE NE Sec. 31 Twp. 29 Rge. 9 (E) (W) W

County Kingman Total Depth 4435

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Co.

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 3:00PM Day 12th Month December Year 1963

The Above well was plugged as follows:

300' of 9 5/8" surface pipe, cemented with 275 sacks. 4434' of 5 1/2" long
string, cemented with 200 sacks. Plug back to 4405'. Top perferation 4385',
Sanded to 4370, bottom cemented with 5 sacks. Hole was filled with mud to
280', 10' rock bridge, cemented with 25 sacks. Hole was filled with mud
to 40', 10' rock bridge, cemented with 10 sacks to base cellar.
3170' of 5 1/2" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging Supervisor

DATE 12/16/63
INV. NO. 8279-11