

223 R

To: 1 110038  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 187-20,407-0000  
SE NW SE, SEC. 5, T 29 S, R 42 W/EX  
1600 feet from S section line  
1410 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5363

Lease Name Nichols Well # 1

Operator: Berexco, Inc.  
Name & Address  
970 Fourth Financial Center  
Wichita, KS 67202

County Stanton 188.50

Well Total Depth 5800 Meramec feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1550

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Beredco, Inc. License Number 5147

Address 401 East Douglas, Suite 402, Wichita, KS 67202

Company to plug at: Hour: 2:10 pm Day: 18 Month: June Year: 1986

Plugging proposal received from Jim Maloney

(company name) Beredco, Inc. (phone) 316-265-2856

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite N/A  
Elevation N/A

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at 400' with 25 sx cement

3rd plug from 40' to surface with 10 sx cement

4th plug to circulate rat hole with 10 sx cement

5th plug to circulate mouse hole with 10 sx cement.

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 4:35 pm Day: 18 Month: June Year: 1986

ACTUAL PLUGGING REPORT 1st plug at 1582' with 50 sx cement, 2nd plug at 412' with 25  
sx cement, 3rd plug from 40' to surface with 10 sx cement, 4th plug to circulate rat hole  
with 10 sx cement, 5th plug to circulate mouse hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Dowell  
(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging RECEIVED  
STATE CORPORATION COMMISSION

DATE JUL 10 1986

Signed James R. Ray (TECHNICIAN)  
JUL - 8 1986

INV. NO. 14311

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84