

To: 1 030714  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 187-00,054-0000  
C SE NW, SEC. 17, T 29 S, R 39 W  
3300 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5952  
Operator: Amoco Production Company  
Name & Address P. O. Box 432  
Liberal, KS 67901

Lease Name Welch Gas Unit Well # "D" 1  
County Stanton 199.23  
Well Total Depth 6130 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 9 5/8 feet 698

Abandoned Oil Well \_\_\_\_\_ Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Midwest Casing Pulling License Number 6497  
Address P. O. Box F, Sublette, KS 67877

Company to plug at: Hour: 9:30 am Day: 26 Month: June Year: 19 86

Plugging proposal received from Ed Eves  
(company name) Midwest (phone) 316-675-8349

were: 7 5/8" at 1744' PBTD 5532' Perfs at 5476-5478'; 5520-5522' 4 1/2" at 5600'

DV Collar at 3026' with 200 sx cement - top of cement at 900'

Fill hole with heavy mud and spot cement through 7 5/8"

Find free point of 4 1/2" casing and pull

1st plug find free point at 7 5/8" and spot 50 sx plug at free point

2nd plug pull 7 5/8" to 50' below shoe joint of 9 5/8" and spot 75 sx cement

3rd plug from 40' to surface with 15 sx cement. Weld plate

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 1:00 pm Day: 7 Month: July Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 870' with 50 sx cement, 2nd plug at 758' with 75 sx cement, 3rd plug from 40' to surface with 10 sx cement.

Recovered 950' 4 1/2" casing and 905' of 7 5/8"

Remarks: Used common cement by Midwest.  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE JUL 14 1986

INV. NO. 14349

JUL 11 1986

CONSERVATION DIVISION  
Wichita, Kansas

Signed Steve Durrant  
(TECHNICIAN)

FORM CP-2/3  
Rev. 01-84