

2 050232

15-095-19080-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 1963
SW-SE, SEC. 34, T 29 S, R 7 W/EX
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Lease Name Walters Well # 4

Operator: Mull Drilling Co., Inc.
Name & Address 221 N. Main, Suite 300
Wichita, KS 67202

County Kingman 137.05

Well Total Depth 4217 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 208 ✓

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Co. Tools License Number _____

Address _____

Company to plug at: Hour: _____ Day: 15 Month: 3 Year: 19 85

Plugging proposal received from _____
(company name) _____ (phone) _____

were: Perforate at 4165' to 82'. Sand back to 4040' and dump 5 sacks of cement. Bridge
in 4 1/2" casing at 275'. Fill with cement inside and outside of 4 1/2"-250 to surface

Plugging Proposal Received by Steve Van Gieson
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:05a.m. Day: 15 Month: 3 Year: 19 85

ACTUAL PLUGGING REPORT Sanded back to 4040 feet and dumped 5 sacks of cement. Did not
pull any casing. Ran 1" pipe down outside of 4 1/2" casing to 280 feet, spot mix and pumped
10 sacks of gel, 2 sacks of hulls. Pulled 1" pipe to 250 feet and circulated cement to
surface. Pulled 1" pipe and ran inside 4 1/2" casing to 250 feet. Circulated cement to
surface.

RECEIVED
STATE CORPORATION COMMISSION
3-20-85
MAR 20 1985

Remarks: Howco Ticket #
(If additional description is necessary, use BACK of this report to observe this plugging.)

Signed Glenn Ward
(TECHNICIAN)

INVOICED
DATE 3-20-85
INV. NO. 7409
3-15

APR 26 1985