

2-10

2-040798

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 15-095-21,009-0000

200' N & 100' W C/2 NE, SECTION 34 TOWNSHIP 29

OPERATOR LICENSE # 31476

4160 FEET FROM S SECTION LINE
2080 FEET FROM E SECTION LINE

OPERATOR BRANOIL COMPANY
NAME & 210 VIRGINIA STREET
ADDRESS PONCA CITY OK 74601

RECEIVED
KANSAS CORPORATION COMMISSION
MAR 09 1995
CONSERVATION DIVISION
WICHITA, KS

LEASE NAME: HOLDER #1
COUNTY: KINGMAN
WELL TOTAL DEPTH: 4210'
PIPE: 4-1/2" @ 4210' 136.83

SURFACE CASING: 8-5/8" @ 240'

ABANDONED OIL WELL GAS WELL INPUT WELL SMD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: DS&W WELL SERVICING INC
ADDRESS: PO BOX 231, CLAFLIN KS 67525 LICENSE: 6901

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: _____

COMPANY NAME: DS&W WELL SERVICING PHONE: 316-

WERE: PERFS 4145'-50' - 35 SX @ 1050' - 35 SX @ 700'-
CIRC CMT 300'

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 13:30 DAY: 10 MONTH: 2 YEAR: 1995

ACTUAL PLUGGING REPORT:
PERFS WERE COVERED W/SAND TO A TOP OF 4100' & CAPPED
W/4 SX CMT - 4-1/2" RECOVERED FROM 3522' & PULLED TO
1075' & 35 SX CMT SPOTTED - 4-1/2" PULLED TO 693' & 35
SX CMT SPOTTED - 4-1/2" PULLED TO 317' & CMT CIRC TO
SURF - REMAINING 4-1/2" PULLED & CMT TOPPED OFF

REMARKS: ALLIED CMT 60/40 4% GEL

I DID OBSERVE THIS PLUGGING.

INVOICED
DATE 3-10-95
INV. NO. 42343

Steve Van Gieson
Steve Van Gieson (AGENT)

FORM CP-2/3
REV. 3/90