

2 090017

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-095-21270-0000

NW SWNE, SEC. 34, T 29 S, R. 7 <sup>West</sup> <sub>W/E</sub>

\_\_\_\_\_ feet from N/S section line

\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6360

Lease Name Holder Well # 2

Operator: Dutton Oil Company

County Kingman

Name & Address 620 First National Center

Well Total Depth 4219 <sup>137.12</sup> feet

Hutchinson, Ks.

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8" feet 318

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Nicholas Casing-Pulling License Number 6698

Address Box 206, Genesio, Ks. 67444

Company to plug at: Hour: \_\_\_\_\_ p.m. Day: 3 Month: 7 Year: 19 84

Plugging proposal received from Alan Nicholas

(company name) Nicholas Casing-Pulling (phone) \_\_\_\_\_

were: sand back 4100'--4 sacks-- bridge 50' sand to 4050'

RECEIVED  
STATE CORPORATION COMMISSION

88 joints 3520' of 4 1/2" recovered

JUL 18 1984

CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by \_\_\_\_\_

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 1:30 p.m. Day: 9 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT The bottom of the hole was filled with sand to 4100' and

5 sacks of cement was spotted on top of sand through the bailer. The pipe was shot off

and 3520' of 4 1/2" was recovered. The top was plugged by pumping 4 sacks of hulls and

10 sacks of Gel and 160 sacks of 50-50 pos, 4% gel and 4% cc to surface.

Remarks: Sun of Medicine Ticket #19084

(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 7-24-84

Signed Dan West  
(TECHNICIAN) no

INV NO. 2613