

2 040134

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-095-20733-0000

TECHNICIAN'S PLUGGING REPORT

80' SW/SE/NE SEC. 3, T 29 S, R 6 NE

1970 feet from NE section line

4290 feet from NE section line

Operator License # 5097

Lease Name Calkins Well # 1

Operator: Martin Oil Produces Inc County Kingman 133.02

Name & Address 1010 Union Center Well Total Depth 4093 feet

Wichita Ks 67202 Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 254 200SK

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address Box 108 Genesco Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Alan Nicholas

(company name) Nicholas Casing Pulling (phone) _____

were:

PBTD 4075' Sand Back to 4010 & 4 SKS cement.
4 1/2 4080' Pump top with 3 Hull, 6 gel 100 SKS Com
Perfs 4063-68 3% cc.

Plugging Proposal Received by W. Kirkpatrick Stull
(TECHNICIAN) Stull

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 200 Day: 26 Month: 11 Year: 19 84

ACTUAL PLUGGING REPORT Sand was dumped down the 4 1/2" casing
to a point 50' above the Perferations at 4010' and 4 sacks
of cement was spotted on top of the cement with a dump
bailer. The 4 1/2 casing was then shot off at 3522' and
recovered. The top was then squeezed by pumping 3 sacks
of Hulls, 6 sacks of Gel and 100 sacks of Common 3% cc

Remarks: Cement. By Halliburton Cementing # 815725
(If additional description is necessary, use BACK of this form.) MAX. 200#
SI. 200#

INVOICED
DATE 12-12-84
INV. NO. 5909

Signed Steve Va Gueson
(TECHNICIAN)