

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

1-31

API NUMBER: 15-191-21,881-00000

W/2 SW NE, SECTION 17 TOWNSHIP 35 RANGE 4W

OPERATOR LICENSE # 30184 3286 FEET FROM S SECTION LINE
OPERATOR CD OPERATING 2342 FEET FROM E SECTION LINE
NAME & 3503 NW 63RD STREET #300
ADDRESS OKLAHOMA CITY, OK 74868 LEASE NAME: DALRYMPLE 2-17

COUNTY: SUMNER 170.62
WELL TOTAL DEPTH: 5250'
PIPE: 4 1/2" @ 5247'
SURFACE CASING: 8 5/8" @ 255'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SELECT WELL SERVICE
ADDRESS: HENNESSEY LICENSE: 32027

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MIKE MOORE
COMPANY NAME: EIGHT ROUND CORPORATION PHONE: _____
WERE: CIBP AT 4850' **RECEIVED**
35 SACKS AT 850' KANSAS CORPORATION COMMISSION
CIRCULATE CEMENT AT 320'

FEB 19 1997

CONSERVATION DIVISION
WICHITA, KS

PLUGGING PROPOSAL RECEIVED BY: STEVE VAN GIESON

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 10³⁰ DAY: 31 MONTH: 1 YEAR: 1997

ACTUAL PLUGGING REPORT: A CIBP WAS SET AT 4850' AND CAPPED WITH 2 SACKS OF CEMENT.
THE 4 1/2" WAS RECOVERED FROM 3000' AND PULLED TO 860' WHERE 35 SACKS OF CEMENT
WAS SPOTTED. THE 4 1/2" WAS PULLED TO 320' WHERE CEMENT WAS CIRCULATED TO
SURFACE.


REMARKS: 60/40 POZ 4% GEL ASC CEMENTING

INVOICED

DATE 2-19-97
INV. NO. 47596

1-31

I DID NOT OBSERVE THIS PLUGGING.



STEVE VAN GIESON