

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

1-24

API NUMBER: 15-191-21,932-0000

C NW NW, SECTION 16 TOWNSHIP 35 RANGE 4W

OPERATOR LICENSE # 30184 4620 FEET FROM S SECTION LINE

OPERATOR CD OPERATING 4620 FEET FROM E SECTION LINE

NAME & 3503 NW 63RD ST., SUITE 300

ADDRESS OKLAHOMA CITY, OK 74868

LEASE NAME: ESTHER 1-16

COUNTY: SUMNER 169.91

WELL TOTAL DEPTH: 5228'

PIPE: 4 1/2" @ 5228'

SURFACE CASING: 8 5/8" @ 289'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SELECT WELL SERVICE

ADDRESS: HENNESSEY, OK LICENSE: 32027

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1997

PLUGGING PROPOSAL RECEIVED FROM: MIKE MOORE

COMPANY NAME: EIGHT ROUND CORP. PHONE: _____

WERE: PERF. 4948'-5110'

PLUGGING PROPOSAL RECEIVED BY: SVG

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL { } PART { } NONE { }

COMPLETED: HOUR: 15:30 DAY: 24 MONTH: 1 YEAR: 1997

ACTUAL PLUGGING REPORT: CIBP SET AT 4900' AND CAPPED WITH 2 SACKS OF CEMENT.
4 1/2" RECOVERED FROM 3528' AND PULLED TO 875' WHERE 35 SACKS OF CEMENT WAS
SPOTTED. PULLED TO 330 AND CIRCULATED TO SURFACE.

REMARKS: 60/40 POZ 4% GEL ASC, CRESENT, OK

INVOICED

RECEIVED
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.

[Signature]
STEVE VAN GIESON

DATE JAN 29 1997 JAN 29 1997

INV. NO. 47481

CONSERVATION DIVISION
WICHITA, KS
MAR 27 1997

aw