

2 040475

1-9

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 19- 191-22,092-0000
C SE NE, SEC. 5, T 35 S, R 4 W X

TECHNICIAN'S PLUGGING REPORT

3300 feet from S section line
660 feet from E section line

Operator License # 3734

Lease Name Nulik Well # 5-1

Operator: Hazelwood Production & Exp.
Name & Address: 6801 N. Broadway, #320

County Sumner 169.33

Oklahoma City, OK 73116

Well Total Depth 5210 feet

Conductor Pipe: Size feet

Surface Casing: Size 8-5/8 feet 272

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Duke Drilling Co. License Number 5929

Address Great Bend, KS 67530

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from John Armbruster

(company name) Duke Drilling (phone)

were: Top of Arb 5180' 35 sx 5150'

RECEIVED STATE CORPORATION COMMISSION

25 sx 1100'

JAN 1 8 1989

25 sx 670'

CONSERVATION DIVISION
Wichita, Kansas

35 sx 320'

25 sx 60' 10 sx R.H.

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 12:15 Day: 9 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT A 35 sx plug of cement was spotted thru drill pipe at

5150' at the top of the Arb at 5180' - the drill pipe was pulled to the bottom

of the salt at 1100' - the top of the salt at 670' was covered with 35 sx of

cement thru the drill pipe - the drill pipe was pulled to 320' where 35 sx of

cement was circ up in the surface - the pipe was pulled from the hole and a

bridge was built at 60' and filled with cement. rat hole was circ with 10 sx.

Remarks: B. J. Titan #512879

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 1-20-89 WK

Signed (TECHNICIAN)

INV. NO. 23737