

2 040535

4-24

10001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 15-095-21,120A D-21,618

NE NW, SEC. 26, T 29 S, R 9W W/E

NE NW feet from S section line

4330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Bohrer Well # B-1

Operator: TXO Production Corp.

County Kingman 150.83

Name & Address 1660 Lincoln St., #1800

Well Total Depth 4641 feet

Denver, CO 80264

Conductor Pipe: Size feet

Surface Casing: Size 8-5/8 feet 265

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

D-21,618

Other well as hereinafter indicated

Plugging Contractor Hays Well Service License Number 5429

Address Attica, KS

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Corey West

(company name) TXO Production Corp (phone)

were: 4-1/2 3132' perms 2936-44' - 2976-86' 3090-3110'

PBTD 3132'

Sand perf. to 2800' & 4 sx - set CIBP 1570' - perf @ 850' 4 shot ft. - pump 100 sx

down 4-1/2" casing (20 sx out)

Plugging Proposal Received by Steve Van Gieson (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 13:30 Day: 24 Month: 4 Year: 19 90

ACTUAL PLUGGING REPORT The perms were sanded off to 2800' and capped w/4 sx cmt -

CIBP set at 1570' & capped w/2 sx cmt - perforations shot at 850' - cmt pumped

down 4-1/2" casing (20 sx) - 2 sx hulls mix in remaining cmt was then followed

w/80 sx cmt. SI 300#

RECEIVED STATE COMMISSION

MAY 25 1990

Remarks: BJ Services #610720 60/40 2% gel

CONSERVATION DIVISION Wichita, Kansas

INVOICED

If additional description is necessary, use BACK of this form.

I (did xxxxxx) observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE 6-6-90

INV. NO. 28346

MK 4-24 JUL 11 1990