

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

9-25

API NUMBER: N/A 11-1756
NW, SW, SE, SECTION 29 TOWNSHIP 29 RANGE 09W

OPERATOR LICENSE # 3048 990 FEET FROM S SECTION LINE
2310 FEET FROM E SECTION LINE

OPERATOR BRISTOL RESOURCES CORP.
NAME & 6655 S. LEWIS #200
ADDRESS TULSA, OK 74136

LEASE NAME: GOETZ, #3
COUNTY: KM Kingman
WELL TOTAL DEPTH: 4460 PB 4429

144.95

PIPE: 5 1/2" @ 4459'

SURFACE CASING: 9.6" @ 240'

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE
ADDRESS: P.O. BOX 209, CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 9:30 DAY: 25 MONTH: 9 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: RICHARD
COMPANY NAME: SAME PHONE: _____

WERE: SAND TO 4325' 5 XS., 35 XS. @ 1400', 35 XS. @ 1000', 300' TO 0'.

PLUGGING PROPOSAL RECEIVED BY: S.V.G.

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (X) PART (_____) NONE (_____)

COMPLETED: HOUR: 1:00 DAY: 25 MONTH: 9 YEAR: 1995

ACTUAL PLUGGING REPORT:
SAND BOTTOM TO 4325' & 5 XS. OF COMMON SHOT 5 1/2"
CASING OFF @ 280'. PULLED TO 1400' PUMPED 35 XS PULLED
TO 1000'. PUMPED 35 XS. PULLED TO 300' PUMPED CMT. TO
SURFACE.

REMARKS: ALLIED #2121 60/40 POZ. 4% GEL.

RECEIVED
KANSAS CORPORATION COMMISSION

I DID OBSERVE THIS PLUGGING.

INVOICED
DATE 10-12-95
INV. NO. 43757-1
9-25

Jack Luthi
Jack Luthi (AGENT)

OCT 17 1995

FORM CP-2/3
CONSERVATION DIVISION
WICHITA, KS