

2-070577

10-9

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER: 9-1956
NW, NW, SE, SECTION 29 TOWNSHIP 29 RANGE 09W

OPERATOR LICENSE # 3048 2302 FEET FROM S SECTION LINE
2538 FEET FROM E SECTION LINE

OPERATOR BRISTOL RESOURCES CORPORATION
NAME & 6655 S. LEWIS, SUITE #200
ADDRESS TULSA, OK 74136

LEASE NAME: GOETZ #1
COUNTY: KM Kingman
WELL TOTAL DEPTH: 4474
PIPE: 5 1/2" @ 4473'

145.41

SURFACE CASING: 9.6" @ 237'

ABANDONED OIL WELL GAS WELL INPUT WELL SWD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____
PLUGGING CONTRACTOR: MIKE'S TESTING & SALVAGE
ADDRESS: BOX 209, CHASE, KS 67524 LICENSE: 31529

COMPANY TO PLUG AT: HOUR: 12:00 DAY: 9 MONTH: 10 YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: RICHARD
COMPANY NAME: BRISTOL RESOURCES CORPORATION PHONE: 918-492-7900
WERE: SAND TO 4360' & 5 XS. 35 XS. @ 1400', 35 XS. @ 1000',
300' TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY: JACK LUTHI
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: _____ DAY: 9 MONTH: 10 YEAR: 1995

ACTUAL PLUGGING REPORT:
SANDED BOTTOM TO 4366' & 5 XS. SHOT 5 1/2" CASING OFF
@ 2221'. PULLED TO 1400' PUMPED 35 XS. PULLED TO 1000'.
PUMPED 35 XS. PULLED TO 300' AND CIRCULATED CMT. TO
SURFACE.

REMARKS: ALLIED #2070 60/40 POZ. 4% GEL.

I DID OBSERVE THIS PLUGGING.

Jack Luthi
Jack Luthi (AGENT)

FORM CP-2/3
REV. 3/90

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 11 1995

CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 10-17-95

INV. NO. 43801
10-9

DW