

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20535-00-00
Spot: CSESENW Sec/Twnshp/Rge: 18-30S-7W
2310 feet from N Section Line, 2310 feet from W Section Line
Lease/Unit Name: WELLS/TOWNER A Well Number: 1
County: KINGMAN Total Vertical Depth: 4330 feet

Operator License No.: 4706
Op Name: MESSENGER PETROLEUM, INC.
Address: 525 S. MAIN ST.
KINGMAN, KS 67068

Conductor Pipe: Size feet: \$140.73
Surface Casing: Size 8.625 feet: 242 200 SX CMT
Production: Size 4.5 feet: 1428 100 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 08/01/2002 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone:

Proposed Plugging Method: Perfs 1349'-59'. Sand to 1300' and 4sxs. 35sxs @ 750'. Circulate 290'.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: Plugging Operations Partially Witnessed
Date/Time Plugging Completed: 08/01/2002 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

The perfs were sand back to 1289' and capped w/4sxs of cement. Casing was recovered from 1004' and pulled to 750' where 35sxs of cement was spotted. Pulled casing to 290' and circulated cement to surface. Pulled remaining casing and topped off cement.

RECEIVED
KCC DISTRICT #2

AUG 02 2002


WICHITA, KS

Remarks: ALLIED CEMENTING 60/40, 4% GEL

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

INVOICED

DATE

8-5-02

INV. NO.

2003060162