

2 040199

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-095-21520-0000

SE 15E SEC. 16, T 30 S, R 7 W

428 feet from N/D section line

380 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003

Lease Name Simons Well # 1

Operator: M<sup>c</sup>Coy Petro Corp.

County Kingman 121.98

Name & Address 500 Heritage Park Place

Well Total Depth 3753 feet

Wichita Ks 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 220

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clark Corp. License Number 5108

Address Medicine Lodge Ks

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Elma Morganstien

(company name) Clark Corp. (phone) \_\_\_\_\_

were:

4 1/2 3751' Sand to 3550' & 4 1/2

Perf 3630-34

PB 3698'

Rec 3161 Top 3 hull. 15 gel 110 <sup>60/40</sup>

Plugging Proposal Received by \_\_\_\_\_ (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 1140 Day: 5 Month: 7 Year: 19 85

ACTUAL PLUGGING REPORT The perforations were shut-off by dumping sand over them, to a top of 3550'. The pipe was shut off and 3161' of 4 1/2 was recovered. The top was squeezed by pumping in the 8 5/8, 3 sacks of hulls, 15 sacks of gel & 110 sacks of 60/40 Poz mix cement.

Remarks: See 283538 (If additional description necessary, use BACK of this form.)

INVOICED

DATE 7-18-85

INV. NO. 9003

RECEIVED STATE CORPORATION COMMISSION  
JUL 16 1985  
Signed by Stacy A. Green  
Wichita, Kansas  
7-16-85  
(TECHNICIAN)  
AO