

15-095-01835-0000

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 60 ✓ R

SEC. 15, T 30S, R 7WE

1320' FEET FROM N/S SECTION LINE

660' FEET FROM W/E SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5618

LEASE NAME R.A. Hopper WELL # 3

OPERATOR: Union Oil Co. of California
NAME & ADDRESS: 2000 Blessen Center
S. Bldg. Okla. City, Okla
73102

COUNTY: Logan

WELL TOTAL DEPTH 4149 FEET \$134.84

CONDUCTOR PIPE: SIZE _____ FEET _____

SURFACE CASING: SIZE 8 5/8" FEET 199'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Gressel Well Services LICENSE NUMBER KCC-347

ADDRESS Haysville, Kansas

COMPANY TO PLUG AT: HOUR: 9⁰⁰ AM DAY: 23 MONTH: 8 YEAR: 19 83

PLUGGING PROPOSAL RECEIVED FROM Man K. Milton

(COMPANY NAME) Union Oil Co. of California (PHONE) 405-528-7624

WERE: Miss. Chat Perf. 4121'-4138' Set 4 1/2" Baker K-1

Cement retainer @ 4085' Squeezed w/ 25 sp below retainer

Stung out of retainer & spot 10 sp on top. Estimated

TOC @ 3955' Displaced hole w/ 9.2[#] 36 vis mud

Perforated 4 1/2" cas. @ 25 PF @ 300'-302' Circulated

Cemented by Haver Ticket # 701959 PLUGGING PROPOSAL RECEIVED BY M.V. Gressel (TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 1⁰⁰ PM DAY: 23 MONTH: 8 YEAR: 19 83

ACTUAL PLUGGING REPORT Miss Chat perf 4121'-4138' Set 4 1/2" Baker

K-1 Cement Retainer @ 4085' Squeezed w/ 25 sp below

retainer Stung out of retainer & spot 10 sp on top.

Estimated TOC @ 3955' Displaced hole w/ 9.2[#]

36 vis mud Perforated 4 1/2" Cas. @ 25 PF

@ 300'-302' Circulated Cmt to surface w/ 15 sp Common

REMARKS Haver Ticket 701959

RECEIVED
STATE CORPORATION COMMISSION
9-2-83
CONSERVATION DIVISION
Wichita, Kansas

I (Q / DID NOT) OBSERVE THIS PLUGGING.

STATE CORPORATION COMMISSION SIGNED M.V. Gressel (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
9-2-83
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

FORM CP-213
REV. 6-83

DATE 9-16-83

INV. NO. 5466-W