

2040454

10-31 15-095-21004-0000

To STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-

S/2 NE, SEC. 31, T 29 S, R 10 W/EX

\_\_\_\_\_ feet from S section line

\_\_\_\_\_ feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Depenbush Well # 1

Operator: TXO Prod. Corp.

County Kingman 88.40

Name & Address 1660 Lincoln St. #1800

Well Total Depth 2720 feet

Denver, CO 80264

Conductor Pipe: Size 8-5/8 feet 266

Surface Casing: Size \_\_\_\_\_ feet

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corp. License Number \_\_\_\_\_

Address Medicine Lodge, KS

Company to plug at: Hour: \_\_\_\_\_ Day: \_\_\_\_\_ Month: \_\_\_\_\_ Year: 19 \_\_\_\_\_

Plugging proposal received from Elmo Morganstjern

(company name) Clarke Corp. (phone) \_\_\_\_\_

were: 2-7/8 2719' 1 hull & 10 sx on bottom

Perf 2621-26' cement plug at 1500' & 500'-0

2632-40'

RECEIVED  
STATE CORPORATION COMMISSION  
STAFF OFFICE

NOV 10 1988  
11-10-88  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by \_\_\_\_\_ (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 10:30 Day: 31 Month: 10 Year: 19 88

ACTUAL PLUGGING REPORT The perforations were plugged off by pumping 1 sx of hulls & 10 sx of cement - the plug was pushed to 1600' and locked up at 2000# - the 2-7/8 was recovered from 1590' - the top was squeezed plugged thru the 8-5/8 surface pipe by pumping 400# of hulls, 5 sx gel, 35 sx cement, 5 sx gel, 100# of hulls and 100 sx of 60.40 poz 2% gel & 2% cc.

Remarks: B.J. Titan #422364 max 700# SI 450#  
(If additional description is necessary, use BACK of this form.)

I (did/did not) observe this plugging.

Signed Steve Van Gieson (TECHNICIAN)

INVOICED  
DATE 11-17-88  
INV. NO. 23013