

2090029

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 095-21.475 - 0000

CSENW _____, SEC. 33, T 29 S, R 10 WXRX

3200 feet from ~~W~~^S section line

3410 feet from ~~E~~^E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Boyd Well # 1

Operator: Hummon Corporation

County Kingman

Name & Address 400 one Main Place

Well Total Depth 4330 140.73 feet

Wichita, Ks.

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8" feet 223' 200

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A XX

Other well as hereinafter indicated _____

Plugging Contractor Bog-H Drilling, Inc. License Number 5148

Address Wichita, Ks.

Company to plug at: Hour: 12:00p.m. Day: 29 Month: 7 Year: 19 84

Plugging proposal received from _____

(company name) K.C.C., Salina (phone) _____

were: _____ to 950', spotted 35 sacks

cement _____ 275' spotted 35 sacks of cement

25 sacks @ 60'; 10 in rat; 10 in mouse

RECEIVED

STATE CORPORATION COMMISSION

AUG 02 1984 Plugging Proposal Received by Toman

(TECHNICIAN)

CONSERVATION DIVISION

Plugging Operations attended by Agent?: All _____ Part _____ None XX

Operations Completed: Hour: 12:30p.m. Day: 29 Month: 7 Year: 19 84

ACTUAL PLUGGING REPORT Filled hole with heavy drilling mud; run drill pipe to

950', spotted 35 sacks of cement through drill pipe; pulled drill pipe to 275' spotted

35 sacks of cement through drill pipe; wood and rubber plug set 60' with 25 sacks of

cement circulated to surface; run one joint of drill pipe in rat hole; circulated 10

sacks of cement to surface; 10 sacks in mouse

Remarks: Sun Cement Ticket #19075 ; 60-40 pos, 2% gel, 3% cc

(If additional description is necessary, use BACK of this form.)

(If desired, you may observe this plugging.)

INVOICED

DATE 8-3-84

Signed Daniel W. [Signature] (TECHNICIAN)

INV. NO. 2863

FORM CP-2/3 Rev. 01-84