

To: 1 100053
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

AP-1 NUMBER 15-187-20,813 - 0000

TECHNICIAN'S PLUGGING REPORT 6-10

Operator License # 5952
Operator: Amoco Production Company
Name:
Address P.O. Box 800
Denver, CO 80201

SE SW NW NE SEC. 35, T 29 S, R 40 W/EX
1000 feet from N& section line
2000 feet from E section line
Lease Name Tiffany Jade Well # 1-35
County Stanton
Well Total Depth 5750 186.87 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1572

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Halliburton License Number _____

Address _____

Company to plug at: Hour: 10 a.m. Day: 10 Month: 6 Year: 19 96

Plugging proposal received from Joe Eudy

(company name) Amoco Production Company (phone) 316-356-1237

logs: 4 1/2" at 5749' w/250 sx cement, PBSD 5710', Perfs at 5616-30'

1st plug set CIBP with 2 sx cement on top at 5575',

Casing pulled apart at 1420'. Casing stub at 1420'.

2nd plug run tubing to 2800' in 4 1/2" casing and pump 220 sx cement,

filling 4 1/2" to 1680' inside and outside. 3rd plug pull tubing to 550' and pump 40 sx,

4th plug at 40' with 10 sx cement

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1 p.m. Day: 10 Month: 6 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug set CIBP at 5575' with 2 sx cement on top,

2nd plug sting tubing inside 4 1/2" casing and run to 2800'. Spotted 220 sx cement, filled 4 1/2"

to 1680' inside and outside.

RECEIVED
KANSAS CORPORATION COMMISSION

3rd plug pulled tubing to 550' and spotted 40 sx cement,

4th plug pulled tubing to 40' and spotted 10 sx cement,

JUN 18 1996

CONSERVATION DIVISION
WICHITA, KS

Remarks: Used 65/35 Pozmix 6% gel by Halliburton. Recovered 1420' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
I would like to observe this plugging.

DATE JUN 24 1996

Signed Gary Winters (TECHNICIAN)

INV. NO. 45851
6-10