

To: 1051764 12-21
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-187-20,710-0000
SW NE NE, SEC. 11, T. 29 S, R. 41 W/X
1100 feet from NE section line
1150 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5703
Operator: J.M. Huber Corporation
Name & Address: 7120 I-40 West, Ste. 100
Amarillo, TX 79106

Lease Name Ruby Arnold Well # 11-1
County Stanton
Well Total Depth 6035 196.14 feet
Conductor Pipe: Size 20 feet 40
Surface Casing: Size 8 5/8 feet 1670

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Murfin Drilling Co. License Number 30606
Address 250 N. Water, Ste. 300, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 20 Month: 12 Year: 19 93

Plugging proposal received from Bill Siddens
(company name) J.M. Huber Corporation (phone) 806-353-9837

Work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 5500' with 50 sx cement, 2nd plug at 1690' with 50 sx cement,
3rd plug at 700' with 40 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X
Operations Completed: Hour: 3:30 a.m. Day: 21 Month: 12 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 5500' with 50 sx cement,
2nd plug at 1690' with 50 sx cement,
3rd plug at 700' with 40 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(if additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION
JAN 03 1994

DATE 1-6-94
INV. NO. 39637
12-21

Signed Richard M. Lacey
CONSERVATION DIVISION
(WICHITA, KANSAS)

EFFECTIVE DATE: 11-17-93
DISTRICT #
SEAT: Yes No

State of Kansas
NOTICE OF INTENTION TO DRILL 15-187-20,710-0000

FORM MUST BE TYPED
FORM MUST BE SIGNED
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date December 5 1993
month day year

Spot SW NE NE Sec 11. Twp 29. S. Rg 41. East West

OPERATOR: License # 5703
Name: J. M. Huber Corporation
Address: 7120 I-40 West, Suite 100
City/State/Zip: Amarillo, TX 79106
Contact Person: William D. Siddens
Phone: 806 353-9837

1100 feet from South / North line of Section
1150 feet from East / West line of Section
IS SECTION X REGULAR IRREGULAR

CONTRACTOR: License #: 30606
Name: Murfin Drilling Co.

(NOTE: Locate well on the Section Plat on Reverse Side)
County: Stanton
Lease Name: Ruby Arnold Well #: 11-1
Field Name: Arroyo (Morrow)

Well Drilled For: Well Class: Type Equipment:
X Oil Enh Rec Infield Mud Rotary
Gas Storage X Pool Ext. Air Rotary
CWFO Disposal Wildcat Cable
Seismic: # of Holes Other

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Morrow/Mississippi
Nearest lease or unit boundary: 1100'
Ground Surface Elevation: 3348! feet MSL

If CWFO: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Water well within one-quarter mile: X yes no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 370!
Depth to bottom of usable water: 550 600

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:
Exp. 5/12/94

Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: (1500') 620
Length of Conductor pipe required: (40') None
Projected Total Depth: 6100'
Formation at Total Depth: Mississippi

Water Source for Drilling Operations:
... well ... farm pond X ... other
DWR Permit #: Purchase from surface owner
Will Cores Be Taken? yes X no
If yes, proposed zone: RECEIVED

AFFIDAVIT 620' Alt. I KANSAS CORPORATION COMMISSION

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher: Gary Trout Bill Siddens
SPUD DATE: 12-8-93 INIT. MSW
LENGTH SURFACE PLANNED: 1675'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? X N SIZE HOLE
SURFACE PIPE 8 3/8 @ 1670 CONDUCTOR 40' of 20"
ANHYDRITE T- B- ELEVATION

TD 6035 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ 5500 Ft. W/ 50 SX
Anhydrite Base @ 1690 Ft. W/ 50 SX
1/2 Base Anyh. @ 200 Ft. W/ 40 SX
1/2, 1/2 Plug @ Ft. W/ SX
Bottom Surface @ Ft. W/ SX
40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W/ 15 SX MOUSE HOLE W/ 10 SX
WATER WELL (Irr. Well Pond Hauling)
TECHNICIAN DATE 12-20-93
TYPE OF EQUIPMENT 40' 40' 60' 60'
STARTING TIME (AM/PM) DATE
COMPLETION TIME 3:30 (AM/PM) DATE 12-21
CEMENT COMPANY Hall