

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 11 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Cook of Imperial Oil Co. has this  
date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Co.

Complete Address: 780 4th Natl. Bldg. Wichita, Ks

Lease Name: Davis Ranch A Well No. 1

Location: 0 NW/SE Sec. 24 Twp. 34s Rge. 15 (E)(W) W

County: Barber Total Depth 2172 Oil Well     

Gas Well      Input Well      SWD Well      D & A      Lost Hole Skid Rig 15 Ft.

Mr. Cook was instructed to plug the well as follows:

350 ft of 8 5/8 surface pipe cemented with 250 sacks--  
circulated. Fill hole to 300 ft, plug, 1/2 sack hulls, 25  
sacks cement. Mud to 40 ft, plug, 1/2 sack hulls, 10 sacks  
cement to surface. 2 sacks cement in rat hole.

Very truly yours,

*Russell Silvester*  
Conservation Division Agent