

State of Kansas

FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 1 1963

CONSERVATION DIVISION  
 Wichita, Kansas

11-1-1963

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. Bryon Catlett of Cherokee Drilling Co. has this  
 date requested permission to plug the following described well:

Mr. Catlett guarantees payment of the plugging fee.

Operator's full Name: Consolidated Petroleum Inc.

Complete Address: 4601 East Douglas, Wichita, Kansas

Lease Name: Davis Ranch "K" Well No. # 1

Location: C SE NE Sec. 4 Twp. 34 Rge. 15 (E) (W) W

County Barber Total Depth 4885 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Catlett was instructed to plug the well as follows:

261' of <sup>10 3/4"</sup> ~~8 5/8"~~ surface pipe, cemented with 225 sacks.

Fill hole with drilling mud to 260', 1st cementing plug,

1/2 sack hulls, cement with 30 sacks. Fill hole with drill-

ing mud to 40', 2nd cementing plug, 1/2 sack hulls, cement

with 15 sacks to base cellar. Bridge and cement rat hole

with 2 sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent