

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bill Musgrove of Bowers Drilling Company has this date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Bowers Drilling Company Inc.

Complete Address: 1434 Wichita Plaza, Wichita, Kansas

Lease Name: Sawyer Well No. # 1

Location: C SE Sec. 33 Twp. 34 Rge. 13 (E) (W) W

County Barber Total Depth 4945 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Musgrove was instructed to plug the well as follows:

350' of 8 5/8" surface pipe, cement circulated with 225 sacks.
Fill hole with drilling mud to 300', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drilling
mud to 40', 2nd cementing plug, bridge with hulls, and cement
with 10 sacks to base cellar. Bridge and cement rat hole with
2 sacks.

Very truly yours,

Archie Elving