

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Trigg of Evans & Trigg has this date requested permission to plug the following described well:

Mr. Trigg guarantees payment of the plugging fee.

Operator's full Name: Evans & Trigg

Complete Address: 410 Woolworth Bldg., Boulder, Colorado

Lease Name: Government Well No. 1-3

Location: SW NW Sec. 3 Twp. 34 Rge. 42 (E)(W)

County: Morton Total Depth 5120' Oil Well X

Gas Well X Input Well SWD Well D & A X Lost Hole

Mr. Trigg was instructed to plug the well as follows:

8 5/8" to 1245' circulated w/ cement. Mud 5120' to 1000'

Spot 35 sacks cement 1000' to 900' Mud 900' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Conservation Division Agent