

1121041 6-18

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-22,475-00-00

C N/2 NW, SEC. 22, T 34 S, R 15 W/E
660 feet from NE section line
1320 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30972

Lease Name Davis Ranch Well # 3-22

Operator: Petroglyph Operating Co., Inc.
Name & Address: P.O. Box 1839
Hutchinson, KS 67504-1839

County Barber 167.38
Well Total Depth 5150 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 804

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Duke Drilling Co., Inc. License Number 5929

Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: _____ Day: 18 Months: 6 Year: 1995

Plugging proposal received from Sally

(company name) Duke Drilling Co., Inc. (phone) 316-267-1331

work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 840' with 50 sx cement, 2nd plug at 400' with 40 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: _____ Day: 18 Month: 6 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 840' with 50 sx cement,
2nd plug at 400' with 40 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

6-23-1995

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(if additional description is necessary, use BACK of this form.)

INVOICED (do not) observe this plugging.

DATE 6-30-95

INV. NO. 43021

Signed Duane Rankin (TECHNICIAN)

RECEIVED STATE CORPORATION COMMISSION JUN 23 1995 CONSERVATION DIVISION WICHITA, KANSAS

FOR THE USE:

FORM C-1 7/91

FORM MUST BE TYPED

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

EFFECTIVE DATE: 6-11-95

State of Kansas

NOTICE OF INTENTION TO DRILL 007-22,475-0000

Must be approved by the K.C.C. five (5) days prior to commencing well

DISTRICT # 1

SEAL Yes No

Expected Spud Date June 7, 1995

OPERATOR: License # 30972
Name: PETROGLYPH OPERATING CO., INC.
Address: P. O. Box 1839
City/State/Zip: Hutchinson, Kansas 67504-1839
Contact Person: Duane Purser
Phone: 316/665-8500

CONTRACTOR: License # 5929
Name: DUKE DRILLING CO., INC.

Well Drilled For: Well Class: Type Equipment:
Oil Enh Rec Infield Mud Rotary
Gas Storage Pool Ext Air Rotary
CWD Disposal Wildcat Cable
Salamic # of Holes Other
If CWD: old well information as follows:
Operator:
Well Name:
Comp. Date: Old Total Depth

Directional, Deviated or Horizontal wellbore? yes X no
If yes, true vertical depth:
Bottom Hole Location:

Exp. 12/6/95

Spot C N/2 NW Sec 22 Twp 34S S. Rg 15W East West
660 feet from XXXX / North line of Section
1320 feet from XXXX / West line of Section
IS SECTION X REGULAR IRREGULAR?
(NOTE: Locate well on the Section Plat on Reverse Side)
County: Barber
Lease Name: Davis Ranch Well #: 3-22
Field Name:
Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Lansing
Nearest lease or unit boundary: 660'
Ground Surface Elevation:
Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no
Depth to bottom of fresh water: 90'
Depth to bottom of usable water: 180'
Surface Pipe by Alternate: X 1 2
Length of Surface Pipe Planned to be set: 240'
Length of Conductor pipe required:
Projected Total Depth: 5150'
Formation at Total Depth: Mississippian
Water Source for Drilling Operations:
DWR Permit #:
Will Cores be Taken? yes X no
If yes, proposed zone:
200' Alt. I Req.

RECEIVED KANSAS CORPORATION COMMISSION

Pusher Sally
SPUD DATE 6-7-95 INIT. Mlu
LENGTH SURFACE PLANNED 240'
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 3/4 @ 80' CONDUCTOR
ANHYDRITE T- B- ELEVATION
TD 4950 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
Arbuckle Plug @ Ft. W/ SX
Hug./Council @ Ft. W/ SX
Anhydrite Base @ Ft. W/ SX
1/2 Base Anyh. @ Ft. W/ SX
1/2, 1/2 Plug @ 42' Ft. W/ 40 SX
Bottom Surface @ 870 Ft. W/ 50 SX
40' Plug @ 42 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN DR DATE 6-16-95
TYPE OF CEMENT 60/10-670
STARTING TIME (AM/PM) DATE
COMPLETION TIME (AM/PM) DATE 6-18-95
CEMENT COMPANIES Hall

RECEIVED STATE CORPORATION COMMISSION JUN 23 1995