

1 040488

11-26

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API-NUMBER 15- Drill Completion Date 9/4/58

W/2 NW, SEC. 36, T 34 S, R 13 W/E
3960 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3048

Lease Name B. Sterling "A" Well # 2

Operator: Bristol Resources Corporation
Name & Address: 6655 South Lewis, Suite 200
Tulsa, OK 74136

County Barber 15863

Well Total Depth 4881 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 282

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Medicine Lodge, KS

Company to plug at: Hour: 9:30 a.m. Day: 26 Month: 11 Year: 19 90

Plugging proposal received from Jeff Clarke

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 4878' w/150 sx cement, PRTD 4877'. Perfs at 4813-71', 2950'

1st plug sanded back from 2950' to 2750' and put 5 sx cement on top of sand bridge through bailer,

2nd plug pump down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:15 a.m. Day: 26 Month: 11 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back from 2950' to 2750' and put 5 sx cement on top of sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 450 psi and shut in 350 psi.

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 1990
12-4-1990
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 2700' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (copy to customer) observe this plugging.

DATE 12-7-90
INV. NO. 30185

Signed Stephen J. Pfeifer (TECHNICIAN)