

TO: 1041288

2-18

15-007-10376-00-00

API NUMBER Drill completion date 10/19/56

STATE CORPORATION COMMISSION SE SE SE, SEC. 36, T 34 S, R 13 W
 CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE
 WICHITA STATE OFFICE BLDG., 130 S. MARKET 330 FEET FROM EAST SECTION LINE
 WICHITA, KANSAS 67202 LEASE NAME Blanche Sterling B WELL # 1
 TECHNICIAN'S PLUGGING REPORT COUNTY Barber 157.53
 OPERATOR LICENSE # 31938 WELL TOTAL DEPTH 4847 FEET
 OPERATOR: Indian Oil Co., Inc. PRODUCTION CSG: SIZE 5 1/2" FEET 4847w/150 sx
 NAME AND P.O. Box 209 SURFACE CASING: SIZE 8 5/8" FEET 266
 ADDRESS Medicine Lodge, KS 67104

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A
 OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR Quality Well Service, Inc. LICENSE NUMBER 31925
 ADDRESS 249 Beth Dr., Sterling, KS

COMPANY TO PLUG AT: HOUR: 1:30 p.m. DAY: 18 MONTH: 2 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM Richard McIntyre
 (COMPANY NAME) Quality Well Service, Inc. (PHONE) 316-727-3410

WERE: Perfs at 4739-44, 4753-58', CIBP @ 4762'

- 1st plug sand back to 4661' and dump 5 sx cement on top of sand through bailer,
- 2nd plug at 600' with 50 sx cement,
- 3rd plug at 300' with 50 sx cement,
- 4th plug at 40' with 10 sx cement.

PLUGGING PROPOSAL RECEIVED BY Steve Pfeifer

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 2:30 p.m. DAY: 18 MONTH: 2 YEAR: 1998

ACTUAL PLUGGING REPORT 1st plug sanded back to 4661' and dumped 5 sx cement on top of sand through bailer,

RECEIVED
STATE CORPORATION COMMISSION

- Spotted plugs through 5 1/2" casing:
- 2nd plug at 600' with 50 sx cement,
- 3rd plug at 300' with 50 sx cement,
- 4th plug at 40' with 10 sx cement. Gel spacer was run between plugs.

FILED 27 1998
2-27-1998
CONSERVATION DIVISION
Wichita, Kansas

REMARKS: Used 50/40 Pozmix 6% gel by Allied. Recovered 3247' of 5 1/2" casing.
 (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.
 DATE 50214
 INV. NO. 50214

SIGNED Stephen J. Pfeifer
 (TECHNICIAN) FORM CP-2/3

INVOICED