

1041289

TO:

2-20

API NUMBER 007-20,302-00-00

STATE CORPORATION COMMISSION C NE NW, SEC. 36, T. 34 S, R. 13 W

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3300 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME Sterling A WELL # 3

TECHNICIAN'S PLUGGING REPORT COUNTY Barber 140.88

OPERATOR LICENSE # 31938 WELL TOTAL DEPTH 4950 FEET

OPERATOR: Indian Oil Co., Inc. PRODUCTION CSG: SIZE 4 1/2" FEET 4947w/125 sx

NAME AND P.O. Box 209 SURFACE CASING: SIZE 8 5/8" FEET 205

ADDRESS Medicine Lodge, KS 67104

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR Quality Well Service, Inc. LICENSE NUMBER 31925

ADDRESS 249 Beth Dr., Sterling, KS

COMPANY TO PLUG AT: HOUR: 11:45 a.m. DAY: 20 MONTH: 2 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM Richard McIntyre

(COMPANY NAME) Quality Well Service, Inc. (PHONE) 316-727-3410

WERE: Perfs at 4855-85'

1st plug sand back to 4792' and dump 4 sx cement on top of sand through bailer,

2nd plug at 600' with 50 sx cement,

3rd plug at 240' with 40 sx cement,

4th plug at 40' with 10 sx cement.

PLUGGING PROPOSAL RECEIVED BY Steve Pfeifer

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:45 p.m. DAY: 20 MONTH: 2 YEAR: 1998

ACTUAL PLUGGING REPORT 1st plug sanded back to 4792' and dumped 4 sx cement on top of sand

through bailer,

Spotted plugs through 4 1/2" casing with gel spacer between plugs:

2nd plug at 600' with 50 sx cement,

3rd plug at 240' with 40 sx cement,

4th plug at 40' with 10 sx cement.

REMARKS: Used 60/40 Pozmix 6% gel by Allied. Recovered 3243' of 4 1/2" casing.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE

SIGNED Stephen J. Pfeifer

(TECHNICIAN) FORM/CP-2/3

INV. NO. 50213

RECEIVED
FEB 21 1998
2-27-1998
CONSERVATION DIVISION
Wichita, Kansas

INVOICED