

1070132

TO: STATE CORPORATION COMMISSION

API NUMBER 15-007-22,249-00-01  
SW SE SEC. 33, T 34 S, R 13 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME GILLIG WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY BARBER 170.95

OPERATOR LICENSE # 5506

WELL TOTAL DEPTH 5260 FEET

OPERATOR: WOOLSEY PETROLEUM CORPORATION PRODUCTION CSG: SIZE 4 1/2" @ 5251' WITH 200 SX

NAME AND PO BOX 168 SURFACE CASING: SIZE 8 5/8" @ 379' WITH 275 SX

ADDRESS MEDICINE LODGE, KS 67104 CONDUCTOR CSG: SIZE " @ ' WITH SX

ABANDONED OIL WELL      GAS WELL X INPUT WELL      SWD WELL      D/A     

OTHER WELL AS HEREINAFTER INDICATED     

PLUGGING CONTRACTOR PRATT WELL SERVICE LICENSE NUMBER 5893

ADDRESS PO BOX 874 PRATT, KS 67124

COMPANY TO PLUG AT: HOUR: 11:20 AM DAY: 19 MONTH: 05 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM CARL DURR

(COMPANY NAME) PRATT WELL SERVICE (PHONE) 316-672-5901

WERE: PERFS AT 4296-4302, 4328-4332, CIBP @ 4260, RETAINER 4845, PERFS AT 4907-4924, 4953-4961, 4732-4742. PERF AT 3855.

CEMENT RETAINER AT 3845' WITH 50 SX CEMENT. PUMP 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8% WIPER PLUG - 100 SX CEMENT. MAXIMUM PRESSURE 400#. SHUT IN PRESSURE 250#.

PLUGGING PROPOSAL RECEIVED BY SCOTT ALBERG

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART      NONE     

OPERATIONS COMPLETED: HOUR: 12:00 PM DAY: 19 MONTH: 05 YEAR: 2000

ACTUAL PLUGGING REPORT     

CEMENT RETAINER AT 3845' WITH 50 SX CEMENT. PUMP 300# HULLS - 10 SX GEL - 50 SX CEMENT - 10 SX GEL - 100# HULLS - 8% WIPER PLUG - 100 SX CEMENT. MAXIMUM PRESSURE 400#. SHUT IN PRESSURE 250#.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 24 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3172' OF 4 1/2" CASING.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM. CONSERVATION DIVISION  
Wichita, Kansas

I (DID) OBSERVE THIS PLUGGING. DATE 5/25/00 SIGNED

(TECHNICIAN) FORM CP-2/3

INVOICED  
61780

*[Handwritten Signature]*