

1 010096

Docket No. D-15,995

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

C E/2 NW NW, SEC. 19, T 34 S, R 13 ^{XX} ~~W/E~~

4620 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4548

Lease Name Graves Well # 2-A SWD

Operator: Oneok Exploration Company

County Barber

Name & Address P. O. Box 871

Well Total Depth 4823 ^{156.75} feet

Tulsa, OK 74102

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 350

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:30 am Day: 28 Month: February Year: 19 86

Plugging proposal received from Millard Kelso

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4800' PBTID 4600' Perfs at 4159-65'; 4575-85'

1st plug sand back to 4100' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, and 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:00 pm Day: 28 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4100' and dumped 4 sx cement on top of sand through bailer. 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 150 sx cement.

Maximum pressure 200 psi and shut in 0

Remarks: Recovered 3260' 4 1/2" casing. Used common cement by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
MAR 12 1986

STATE CORPORATION COMMISSION

Signed 
(TECHNICIAN)

DATE

MAR 11 1986

INV. NO. 12944

CONSERVATION DIVISION
Wichita, Kansas