

1100281

TO: STATE CORPORATION COMMISSION 3-11

API NUMBER 15-129-10,361-0000
C NW SEC. 31, T 34 S, R 42 W

CONSERVATION DIVISION - PLUGGING SECTION 1315 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1301 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME HEINTZ WELL # 1-31

TECHNICIAN'S PLUGGING REPORT COUNTY MORTON

OPERATOR LICENSE # 6594 WELL TOTAL DEPTH 3160 102.70 FEET

OPERATOR: COASTAL OIL & GAS PRODUCTION CSG: SIZE 5 1/2" @ 3070 WITH 300 SX

NAME AND 9 GREENWAY PLAZA #2751 SURFACE CASING: SIZE 8 5/8" @ 605' WITH 350 SX

ADDRESS HOUSTON, TX 77046

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENT AND HORTON PLUGGING LICENSE NUMBER 31151

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 11 MONTH: 03 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT AND HORTON PLUGGING (PHONE) 580-854-6515

WERE: PERFS AT 2648-2966

1ST PLUG SET CIBP @ 2600' WITH 2 SX CEMENT ON TOP.

2ND PLUG SPOT 60 SX CEMENT AT 630'.

3RD PLUG SPOT 10 SX AT 40'.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART X NONE

OPERATIONS COMPLETED: HOUR: 3:00 PM DAY: 11 MONTH: 03 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 2600' WITH 2 SX CEMENT ON TOP.

2ND PLUG SPOT 60 SX CEMENT AT 630'.

3RD PLUG SPOT 10 SX CEMENT AT 40'.

3-2-1997

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED 730' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 4-2-99

SIGNED Gary Winters (TECHNICIAN) FORM CP-2/3

INV. NO. 60760

INVOICED