

1100291

TO: STATE CORPORATION COMMISSION 4-16

API NUMBER 15-129-21,399-00-00  
C SE SEC. 31, T 34 S, R 42 W

CONSERVATION DIVISION - PLUGGING SECTION 1320 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1320 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME GREEN WELL # 2-31

TECHNICIAN'S PLUGGING REPORT

COUNTY MORTON 108.13

OPERATOR LICENSE # ~~6594~~ 6593

WELL TOTAL DEPTH 3327 FEET

OPERATOR: COASTAL OIL & GAS PRODUCTION CSG: SIZE 5 1/2" @ 3327 WITH 450 SX

NAME AND 9 GREENWAY PLAZA #2751 SURFACE CASING: SIZE 8 5/8" @ 1481' WITH 820 SX

ADDRESS HOUSTON, TX 77046

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR DOWELL LICENSE NUMBER NA

ADDRESS 6601 BROADWAY EXT., SUITE 200, OKLAHOMA CITY, OK 73116-8214

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 16 MONTH: 04 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM TRENT MITCHELL

(COMPANY NAME) DOWELL (PHONE) 405-840-1621

WERE: PERFS AT 2661-2992

1ST PLUG SET CIBP @ 3070'

2ND PLUG MIX 600# HULLS AND 315 SX CEMENT TO FILL 5 1/2" TO SURFACE AT 506 PSI.

3RD PLUG MIX 40 SX CEMENT TO PRESSURE 8 5/8" X 5 1/2" ANNULAS TO 497 PSI.

CEMENT AT SURFACE ON BOTH SIDES.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 1:00 PM DAY: 16 MONTH: 04 YEAR: 1999

ACTUAL PLUGGING REPORT

1ST PLUG SET CIBP AT 3070'.

2ND PLUG MIX 600# HULLS AND 315 SX CEMENT TO FILL 5 1/2" TO SURFACE AT 506 PSI.

3RD PLUG MIX 40 SX CEMENT TO PRESSURE 8 5/8" X 5 1/2" ANNULAS TO 497 PSI.

CEMENT AT SURFACE ON BOTH SIDES.

REMARKS: USED 60/40 POZMIX 6% GEL BY DOWELL. NO CASING RECOVERED.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

INVOICED RECEIVED  
I (DID) OBSERVE THIS PLUGGING. TECHNICIAN

SIGNED Gary Winters (TECHNICIAN) FORM CP-213

DATE 5-7-99 MAY 04 1999

INV. NO. 60922 CONSERVATION DIVISION 5-4-1999  
4-16 AUG 27 1999