

020222

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- NA
NW SE NE, SEC. 8, T 34 S, R 42 W
3630 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Interstate Well # E-1

Operator: OXY USA

County Morton 151.52

Name & Address P.O. Box 26100

Well Total Depth 4662 feet

Oklahoma City, OK 73126-0100

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1245

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargents Casing Pulling License Number 6547

Address P.O. Box 506, Liberal, KS 67901

Company to plug at: Hour: 1 p.m. Day: 12 Month: 3 Year: 1989

Plugging proposal received from Don Horton

(company name) Sargents Casing Pulling (phone) 316-624-7455

were: 4 1/2" at 4507' PBD 4441' Perfs at 4243-49' DV'd at 3193' w/150 sx cement

RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1989
3-24-1989

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 4 p.m. Day: 13 Month: 3 Year: 1989

ACTUAL PLUGGING REPORT 1st plug set GIBP at 4050' w/35' cement on top,

2nd plug pulled 4 1/2" casing, ran tubing to 1450', pumped 50 sx cement,

3rd plug pulled tubing to 1295' and pumped 50 sx cement,

4th plug pulled tubing to 700' and pumped 20 sx cement,

5th plug pulled to tubing to 40', circulated 10 sx cement to surface.

Remarks: Used common cement by Sargent's. Recovered 1400' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED (If not) observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE 3-27-89

INV. NO. 24237