

1100328

TO: STATE CORPORATION COMMISSION

API NUMBER 15-129-21,562-0000
C NW NE SEC. 16, T 34 S, R 42 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 1980 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SANTA FE C WELL # 3

TECHNICIAN'S PLUGGING REPORT

COUNTY MORTON 162.50

OPERATOR LICENSE # 5447

WELL TOTAL DEPTH 5000 FEET

OPERATOR: OXY USA INC. PRODUCTION CSG: SIZE 5 1/2" @ 4373' WITH 185 SX

NAME AND PO BOX 2528 SURFACE CASING: SIZE 8 5/8" @ 1282' WITH 450 SX

ADDRESS LIBERAL, KS 67905-2528

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC LICENSE NUMBER 31151

ADDRESS RT. 1, BOX 49BA, TYRONE, OK 73951-9731

COMPANY TO PLUG AT: HOUR: 8:00 AM DAY: 27 MONTH: 01 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM DON HORTON

(COMPANY NAME) SARGENT & HORTON PLUGGING, INC (PHONE) 580-854-6515

WERE: PERFS AT 4263-68

1ST PLUG PUMP 100# HULLS WITH 25 SX CEMENT TO PLUG PERFS AT 4263' TO 4063'.

2ND PLUG SPOT 50 SX CEMENT AT 1330'. 3RD PLUG SPOT 40 SX CEMENT AT 400'.

4TH PLUG SPOT 10 SX CEMENT FROM 40' TO 0'.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 4:30 PM DAY: 28 MONTH: 01 YEAR: 2000

ACTUAL PLUGGING REPORT _____

1ST PLUG PUMP 100# HULLS WITH 25 SX CEMENT TO PLUG PERFS AT 4263' TO 4063'.

2ND PLUG SPOT 50 SX CEMENT AT 1330'. 3RD PLUG SPOT 40 SX CEMENT AT 400'.

4TH PLUG SPOT 10 SX CEMENT FROM 40' TO 0'. GOOD CIRCULATION ON ALL PLUGS. RECEIVED

STATE CORPORATION COMMISSION

FEB - 3 2000

REMARKS: USED COMMON CEMENT BY SARGENTS. RECOVERED ²¹⁰⁴ of 5 1/2" CASING CONSERVATION DIVISION
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.) in, Kansas

I (DID) OBSERVE THIS PLUGGING.

INVOICED

DATE 2/3/00 SIGNED _____

Gary Winters
(TECHNICIAN)

FORM CP-2/3

INV. NO. 06/210