

176 R

To: 020022
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-20,733-00-00
SE SE SE, SEC. 22, T 34 S, R 42 W EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Operator: Cities Service Oil & Gas Corp.
Name &
Address 3545 N.W. 58th Street
Oklahoma City, OK 73112

554 feet from S section line

554 feet from E section line

Lease Name Cushman A Well # 2

County Morton 160.88

Well Total Depth 4950 Chester feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1347

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address 620 S. Lincoln, Box 506, Liberal, KS 67901

Company to plug at: Hour: 2:30 pm Day: 16 Month: July Year: 1986

Plugging proposal received from Robert Sargent

(company name) Sargent's (phone) 316-624-7455

were: 5 1/2" at 4940' PBD 4877' Perfs at 4464-68' Elevation 3500' Anhydrite 1347'

- 1st plug CIBP at 4455' with 2 sx cement on top through bailer
- 2nd plug between 3028' and 2910' with 40 sx cement
- 3rd plug at 1400' spot 50 sx cement
- 4th plug at 700' spot 30 sx cement
- 5th plug from 40-0' with 10 sx cement

Plugging Proposal Received by Glenn R. Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 4:00 pm Day: 17 Month: July Year: 1986

ACTUAL PLUGGING REPORT 1st plug CIBP at 4420' with 2 sx of cement through bailer,
2nd plug at 2600' with 25 sx of cement, 3rd plug at 1390' with 50 sx cement,
4th plug at 710' with 30 sx cement and 5th plug from 40' to surface with 10 sx
cement. The cap was welded on.

Good circulation during spotting of plugs.

Remarks: Recover 2614' of 5 1/2" casing, 2000' of 50 Pozmix by Sargent's.
(If additional description is necessary, use BACK of this form.)

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-24-86

INV. NO. 14508

Signed Glenn R. Barlow (TECHNICIAN)

JUL 24 1986

7-24-1986