

1 050512

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION NE SE _____, SEC. 22 _____, T 34 S, R 42 W/EX
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 129-20,726-0000

TECHNICIAN'S PLUGGING REPORT

1980 feet from S section line
510 feet from E section line

Operator License # 5447
Operator: Cities Service Oil & Gas Corp.
Name & Address: 3545 NW 58th Street
Oklahoma City, OK 73112

Lease Name Cushman A Well # 1
County Morton 159.90
Well Total Depth 4920 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1367

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 3:00 pm Day: 2 Month: May Year: 19 85

Plugging proposal received from Doug Blair

(company name) Sargent's (phone) 316-624-7455

were: 5 1/2" at 3804' PBTD 3762' Perfs at 3513-3517'

1st plug set CIBP at 3500' with 2 sx cement
Pump through 5 1/2" casing with mud between plugs
2nd plug at 2440' with 25 sx cement 3rd plug at 1400' with 50 sx cement
4th plug at 600' with 40 sx cement
solid bridge
5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

Plugging Proposal Received by Richard W. Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:30 pm Day: 2 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug set CIBP at 3500' with 2 sx cement, 2nd plug at 2440' with 25 sx cement, 3rd plug at 1400' with 50 sx cement, 4th plug at 600' with 40 sx cement, 5th & 6th plugs - solid bridge: - hulls - plug at 40' -- cement to surface with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1985
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 2519' 5 1/2" casing. Used common cement by Sargent's
(If additional description is necessary, use BACK of this form.)

5-13-1985

INVOICED

DATE 5-14-85

Signed Richard W. Lacey
(TECHNICIAN)

INV. NO. 8111

5-2 JUN 6 1985