

1 100132

5-27

API NUMBER 15- 129-21,048 000-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

NW NW SE, SEC. 22, T 34 S, R 42 W/E
2310 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Federal A Well # 1-22

Operator: OXY USA Inc.

County Morton 160,94

Name & Address P.O. Box 300

Well Total Depth 4952 feet

Tulsa, OK 74102

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1514

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Gibson Well Service License Number 5866

Address Liberal, KS

Company to plug at: Hour: 9:30 a.m. Day: 27 Month: 5 Year: 19 97

Plugging proposal received from Dan Cox

(company name) OXY USA Inc. (phone) 316-629-4219

Work: 5 1/2" at 4952' w/440 sx cement, PBSD 4912', Perfs at 4409-12', Squeezed @ 4417-20' w/75' sx cement

1st plug pump 50 sx cement down backside,

2nd plug set CIBP at 4385' and spot 8 sx cement on top through tubing,

3rd plug spot 15 sx cement at 2980', 4th plug spot 45 sx cement at 1620',

5th plug spot 35 sx cement at 550', 6th plug spot 10 sx cement at 70'.

Plugging Proposal Received by Scott Alberg (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 3:30 p.m. Day: 27 Month: 5 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4380' with 8 sx cement on top, displace w/gel,

2nd plug spot 15 sx cement from 3035-2920' through tubing,

3rd plug spot 45 sx cement from 1620-1272' through tubing, displace with gel,

4th plug spot 35 sx cement from 550-300' through tubing, displace with gel,

5th plug topped off with 10 sx cement from 70-0'.

6th plug ran 1" down 8 5/8" X 5 1/2" to 40', cemented to surface.

Remarks: Used Premium Lite cement by Halliburton. No casing recovery.

If additional description is necessary, use BACK of this form.)

I (did not observe this plugging.

DATE JUN 06 1997

Signed Gary Winter (TECHNICIAN)

INV. NO. 48254 AUG 21 1997