

To: 1051602
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App. 12-2
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-21,100-0000 10516
NE NW SE, SEC. 24, T 34 S, R 42 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447
Operator: OXY USA INC.
Name:
Address P.O. Box 26100
Oklahoma City, OK 73126-0100

2410 feet from S section line
1650 feet from E section line
Lease Name Brown F Well # 3
County Morton 116640
Well Total Depth 5120 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1418

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____
Plugging Contractor Halliburton License Number _____
Address _____

Company to plug at: Hour: 11 a.m. Day: 2 Month: 12 Year: 19 92

Plugging proposal received from Rick Frederick
(company name) OXY USA INC. (phone) 316-697-4427

Perfs: 5 1/2" at 5123'-1st stage 440 sx cement, DV: at 3117' w/510 sx cement, PBTD 5075'
Perfs at 4911-4956'

1st plug set CIBP at 4900' with 2 sx cement on top,
2nd plug spot plugs through tubing, fill hole with mud and pump 50 sx cement at 1520',
3rd plug perforate Day Creek Dolomite at 581-594', fill hole with mud and pump 30 sx cement at
700', 6 sx cement at 40'. Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____
Operations Completed: Hour: 1 p.m. Day: 2 Month: 12 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4900' and dumped 2 sx cement on top,
Spot plugs through tubing:
2nd plug filled hole with mud and pumped 50 sx cement at 1520',
Perforated Day Creek Dolomite at 581-594', tested water for 5 days, filled hole with mud again,
3rd plug pumped 30 sx cement at 700',
4th plug pumped 6 sx cement at 40'.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. No casing recovery.
(if additional description is necessary, use BACK of this form.)

INVOICED
(if necessary) observe this plugging.

DATE 1-14-93
INV. NO. 37205
12-2

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
DEC 4 1992

CONSERVATION DIVISION
Wichita, Kansas