

1 030944

4-29-88

API NUMBER 15- 129-20,910-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

N/2 SW SW, SEC. 25, T. 34 S, R. 42 W/E

990 feet from S section line

4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Thompson G Well # 2

Operator: Oxy USA, INC  
Name & Cities Service Oil & Gas Corp.

County Morton 165.10

Address 3545 N.W. 58th Street

Well Total Depth 5080 feet

Oklahoma City, OK 73112

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 1415

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H-30 Drilling Inc. License Number 5107

Address 251 North Water, Suite 10, Wichita, KS 67202

Company to plug at: Hour: 8 p.m. Day: 29 Month: 4 Year: 19 88

Plugging proposal received from Kyle Wylie

(company name) Cities Service Oil & Gas Corp. (phone) 316-624-1892

work: to fill hole with heavy mud and spot cement through drill pipe Elevation 3485'

1st plug at 3200' with 100 sx cement, 2nd plug at 1440' with 50 sx cement,

3rd plug at 500' with 35 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 11 p.m. Day: 29 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug at 3200' with 100 sx cement,

2nd plug at 1440' with 50 sx cement,

3rd plug at 500' with 35 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION

MAY 13 1988

CONSERVATION DIVISION  
Wichita, Kansas

Signed Steve Durrant  
(TECHNICIAN)

INVOICED

DATE 5-17-88

INV. NO. 20626

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date. April 15, 1988

API Number 15-129-20,910-0000

OPERATOR: License # 5447
Name: Cities Service Oil & Gas Corporation
Address: 3545 N.W. 58th Street
City/State/Zip: Oklahoma City, OK 73112
Contact Person: Raymond Hui
Phone: (405) 949-4268

N/2 SW/4 SW/4 Sec. 25 Twp. 34 S. Rg. 42
990 Ft. from South Line of Section
4620 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 990 feet
County: Morton

CONTRACTOR: License # H-30 #3
Name: Unknown at this time
City/State:

Lease Name: Thompson G Well #: 2
Ground surface elevation: 3485 feet MSI.

Well Drilled For: Oil Storage Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

If OWWO: old well info as follows:
Operator:
Well Name:
Comp Date: Old Total Depth:

Depth to bottom of fresh water: 300
Depth to bottom of usable water: 450

Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set: 1375'
Conductor pipe required: 55'
Projected Total Depth: 5080'
Producing: Morrow L

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date: 3-31-88 Signature of Operator or Agent: Raymond Hui, Accounting Control Analyst

For KCC Use:
Conductor Pipe Required: feet; Minimum Surface Pipe Required: 450 feet per Alt.
This Authorization Expires: 10-1-88 Approved By: Ret 4-1-88

EFFECTIVE DATE: 4-6-88
Spud 4-21-88
Set 1415 8:30

APR 10 10:10 AM
N/2 SW/4 SW/4 Sec. 25 Twp. 34 S. Rg. 42

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 3 columns: Plug depth (ft.), Formation, and Footage (ft.). Rows include 1st plug @ 3200 ft. deep, 2nd plug @ 1470 ft. deep, 3rd plug @ 500 ft. deep, 4th plug @ 40 ft. deep, and 5th plug @ ft. deep.

(2) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

Handwritten notes and logs:
PUSHER: Note, C-11, W 1/2 of Cities
TD: 5080 FORMATION Morrow
SURFACE PIPE: 8 3/8 @ 1415'
ANHYDRITE: ELEVATION 3485
STARTING TIME & DATE: 4-29-88 8:00 PM
COMPLETION TIME & DATE: 4-29-88 11:00 PM
1st PLUG @ 3200 FT. W/ 100 SX
2nd PLUG @ 1440 FT. W/ 50 SX
3rd PLUG @ 500 FT. W/ 35 SX
4th PLUG @ 40-0 FT. W/ 10 SX
RAT HOLE CIRCULATED W/ 15 SX
MOUSE HOLE CIRCULATED W/ 10 SX
WATER WELL PLUGGED W/ SX
CEMENT COMPANY: Hall 6/9/40 w/ 6 3/8"
TECHNICIAN: A.D.

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1988
CONSERVATION DIVISION
Wichita, Kansas