

77R

To: 1 020029
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-20,824-00-00
C W/2 NE SW, SEC. 25, T 34 S, R 42 (W) EX
1980 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Snead A Well # 1
County Morton 165.43

Operator: Cities Service Oil & Gas Corporation
Name & Address 3545 NW 58th Street
Oklahoma City, OK 73112

Well Total Depth 5090 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1421

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A X

Other well as hereinafter indicated _____

Plugging Contractor Halliburton Services License Number 5287

Address Box 1598, W.Hwy 54, Liberal, KS 67901

Company to plug at: Hour: 7:30 p.m. Day: 13 Month: 9 Year: 19 86

Plugging proposal received from Steve Cole

(company name) Halliburton (phone) 316-624-3879

were: to fill hole with heavy mud and spot cement through drill pipe

- 1st plug at 3200' with 55 sx cement
- 2nd plug at 1470' with 50 sx cement
- 3rd plug at 900' with 50 sx cement
- 4th plug at 40' with 10 sx cement
- 5th plug to circulate rathole with 15 sx cement
- 6th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 10:30 p.m. Day: 13 Month: 9 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 4607' with 50 sx cement
2nd plug at 3212' with 55 sx cement
3rd plug at 1476' with 50 sx cement
4th plug at 700' with 40 sx cement, 5th plug at 40' with 10 sx cement
5th plug to circulate rathole with 15 sx cement

Remarks: Used 60/40 Pozmix 2% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED (add) observe this plugging.

Signed *Shawn R. Barlow* (TECHNICIAN)

DATE 9-19-86

INV. NO. 14976 9-13

SEP 28 1986

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

yes

Starting Date September 6, 1986 month day year

API Number 15-129-20,824-0000

OPERATOR: License # 5447
Name Cities Service Oil and Gas Corporation
Address 3545 NW 58th Street
City/State/Zip Oklahoma City, OK 73112
Contact Person Raymond Hui
Phone (405) 949-4432

C 1/2 NE SW Sec. 25 Twp. 34 S, Rg. 42
1980' Ft. from South Line of Section
3630' Ft. from East Line of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License #
Name Unknown at this time
City/State

Nearest lease or unit boundary line 1650' feet
County Morton
Lease Name Snead A Well # 1
Ground surface elevation Est. 3485' feet MSL
Domestic well within 330 feet yes X no
Municipal well within one mile yes X no
Surface pipe by Alternate 1 X 2
Depth to bottom of fresh water 350
Depth to bottom of usable water 350 500
Surface pipe planned to be set 1370'
Projected Total Depth 5090' feet
Formation Upper Morrow L-1 Sand

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj X Pool Ext Air Rotary
OWWO Expl Wildcat Cable

If OWWO: old well info as follows:

Operator
Well Name
Comp Date Old Total Depth Producing

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

cementing will be done immediately upon setting production casing.

Date 8/22/86 Signature of Operator or Agent Raymond Hui Title Accounting Control Analyst

For KCC Use:

Conductor Pipe Required feet; Minimum Surface Pipe Required 5.5D feet per Alt.
This Authorization Expires 2-25-87 Approved By 8-25-86
spud 9-3-86 S.P. at 1425' WW yes

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

Table with 4 columns: Plug depth, feet depth with, size of, and material. Rows include 1st plug @ 3200, 2nd plug @ 1470, 3rd plug @ 780-900, 4th plug @ 40, 5th plug @ 15, and (2) Rathole with 15.

Vertical form fields for PUSHER, TD, SURFACE PIPE @, ANHYDRITE ELEVATION, STARTING TIME & DATE, PLETION TIME & DATE, 1st PLUG @ FT. W/ SX, 2nd PLUG @ FT. W/ SX, 3rd PLUG @ FT. W/ SX, 4th PLUG @ FT. W/ SX, RAT HOLE CIRCULATED W/ SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY, and TECHNICIAN.

SEP 18 1986