

To: 1 020419 15-129-10548-0000
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-20
API NUMBER 15- Drill Completion Date 1/15/59 251

C SE SW, SEC. 26, T. 34 S, R. 42 W. 152.75
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4549

Lease Name Taloga Mor "G" Well # 202

Operator: Anadarko Petroleum Corporation
Name & Address P.O. Box 351
Liberal, KS 67905-0351

County Morton

Well Total Depth 4700 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1418

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Sargent's Casing Pulling License Number 6547

Address 620 S. Lincoln, Liberal, KS 67901

Company to plug at: Hour: 9:30 a.m. Day: 19 Month: 9 Year: 19 91

Plugging proposal received from Marvin Johnson

(company name) Anadarko Petroleum Corporation (phone) 316-697-2188

were: 5 1/2" at 4699' w/450 sx cement, PBTD 4610', Perfs at 4542-76'

1st plug pump 1 sx hulls and 25 sx cement with tubing,

2nd plug pump 30 sx cement at 2400',

3rd plug pump 40 sx cement at 1460',

4th plug pump 30 sx cement at 650', 5th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 4 P.m. Day: 20 Month: 9 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug pumped 1 sx hulls and 25 sx cement with tubing,

2nd plug pumped 30 sx cement at 2400',

3rd plug pumped 40 sx cement at 1460',

4th plug pumped 30 sx cement at 650',

5th plug pumped 10 sx cement at 40'.

RECEIVED
STATE CORPORATION COMMISSION

NOV 4 1991

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Sargents. Recovered 2408' of 5 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 11-8-91

Signed Glenn R. Barlow
(TECHNICIAN)

INV. NO. 33637