

1.030187

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-129-20,708 *Ro*

E/2 SE NW, SEC. 26, T 34 S, R 42 *W/E*

1980 feet from N/E section line

2130 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5447

Lease Name Riley D Well # 2

Operator: Cities Service Oil & Gas Corp.

County Morton

Name & Address 3545 N.W. 58th Street

Well Total Depth 5006 *162.70* feet

Oklahoma City, OK 73112

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 1392

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Wakefield Oil Company License Number 5662

Address 300 West Douglas, Wichita, KS 67202

Company to plug at: Hour: 12:00 pm Day: 30 Month: May Year: 19 84

Plugging proposal received from Dan Cox

(company name) Wakefield (phone) 316-264-2366

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 4550 with 50 sx cement

2nd plug at 3100' with 70 sx cement

3rd plug at 1443' with 40 sx cement

4th plug at 950' with 40 sx cement

5th plug - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rat hole Plugging Proposal Received by *Steve Purant*
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5:15 am Day: 31 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 4550' with 50 sx cement, 2nd plug at 3100' with 70

sx cement, 3rd plug at 1443' with 40 sx cement, 4th plug at 950' with 40 sx cement, 5th

& 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement,

7th plug to circulate rat hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 01 1984

Remarks: Used Class H Cement by Dowell.

(if additional description is necessary, use BACK of this form) *Wichita* Kansas

CONSERVATION DIVISION

INVOICED

DATE 6-6-84

INV. NO. 1893

5-81

JUN 18 1984

Signed *Steve Purant*
(TECHNICIAN)